BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

NEGOTIATED SCHEDULE - B

PACKAGE No-01 Development of Yelahanka Govt Degree collage and Ayurvedic Hospital and Providing Grill Fencing and other developmental works to Rajiv Gandhi park, tree park, Nethaji park, Basaveshwara park, judicial layout park and someshwara hill of Yelahanka Assembly Constituency Under Amrutha Nagarothana Grants

SNo	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
1	8.31	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineer-in-charge.(Volume II Item -19.7.3 Pg no 163)	Cum	910.39	Rupees Nine Hundred Ten And Paise Thirty Nine Only
2	3.15	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking to the appropriate disposal area as per direction of Engineer-in-charge. (Volume II, Item No. 19.13.2 , Page No. 164)	Sqm	109.62	Rupees One Hundred Nine And Paise Sixty Two Only
3	5.09	Providing Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work. (Volume II , Item No. 6.4 , Page No. 13)	Cum	8612.30	Rupees Eight Thousand Six Hundred Twelve And Paise Thirty Only
4	271.02	Providing 18 mm cement plaster in two coats under layer 12 mm thick cement plaster with cement mortar 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster with cement mortar 1:3 (1 cement : 3 coarse sand) finished rough with sponge to brick masonry including rounding off corners wherever required smooth rendering, providing andremoving scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. (Volume II , Item No. 8.9 , Page No. 42)	Sqm	379.62	Rupees Three Hundred Seventy Nine And Paise Sixty Two Only
5	1107.27	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two coats) over and including water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.s (Volume II, Item No. 8.25 , Page No.45)	Sqm	121.16	Rupees One Hundred Twenty One And Paise Sixteen Only
6	1963.74	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m^2 over and including priming coat of exterior primer applied @ 2.20 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge(Volume III Item no - 8.30 Pgno 46)	Sqm	156.92	Rupees One Hundred Fifty Six And Paise Ninety Two Only
7	3.15	Providing and fixing in position fully panelled Honne wood shutters for doors with , stiles and rails of 35mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures) (Volume II , Item No. 12.17 , Page No.100)	Sqm	5614.61	Rupees Five Thousand Six Hundred Fourteen And Paise Sixty One Only
8	12.76	Painting wood work with Deluxe Multi Surface Paint of required shade. Two coat applied @ 0.90 ltr/10 m^2 over an under coat of primer applied @0.75 ltr/10 m^2 of approved brand and manufacture to give an even shade including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, sand papering and knotting , cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Volume II , Item No. 8.33.2 , Page No.46)	Sqm	121.16	Rupees One Hundred Twenty One And Paise Sixteen Only

Contractor

Haley D D

Scanned by TapScanner

o	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
9	161.47	Providing & Fixing of Mineral Fibre Suspended Ceiling System in the module size of 600x600x19mm with Exposed grid for Hospitals, Shopping malls, Commercial establishments and office complexes.The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance 87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, NRC -0.7,Colour White, Fire Performance UK A2 S1, dO, with Anti Microbial coating on the face of the tile, suitable for zone 4 area according to NF S 90-35:2003 with cleanroom class of ISO 5 (Class 100), Decontamination Class of CP1Oand Bacteriological Cleanliness Class B1 for specific strains and reduction in colony size. Washability properties of 500 wash cycles as per ASTM D-4828 and suitable for Green Building application with Recycled content of 37%. The tile shall be laid on 24mm wide T - section flanges colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 38mm and a load carrying capacity of 15 kg/m2 & pull out strength of minimum 100 kg The T Sections should have a Galvanizing of 90 grams per m2 and need to be installed with suspension system of approved make (Volume III Item No 7.50 Pg No	Sqm	2141.54	Rupees Two Thousand One Hundred Forty One And Paise Fifty Four Only
10	247.50	Providing and supplying 'Acoustical Wall Paneling' with square edges made of fibre glass substrate 25mm thick and wrapped on the front side with an acoustically transparent and classified for Fire reaction Class A, as per ASTM E-84, fabric with option of colors - as per the choice of the Architect/Engineer incharge of the size 600x600mm, 600x1200mm & 600x1800mm providing a minimum sound absorptionlevel of 0.85 NRC to be affixed to wall using Wall panel Impaler sand construction adhesives as per the instructions laid down by the certified manufacturer. (Volume II Pg - 32 Item 7.51)	Sqm	4999.62	Rupees Four Thousand Nine Hundred Ninety Nine And Paise Sixty Two Only
11	25.00	Sharing workstation 2B) Size : 1200 mmW x 540mm D x 1200 mm ht - (Sharing-Postformed table top): Back to Back (set of 2) Item 39.15.2 Pg no-332	Nos	25784.03	Rupees Twenty Five Thousand Seven Hundred Eighty Four
12	25.00	Mobile pedestal unit- WOODEN : Providing and fixing 450mmw X 450 mmd X 685 mmht) Mobile pedestal unit-WOODEN with 18mm thick PLPB with edge bonded for body, Two equal drawer and filing drawer with centralized locking system, Telescopic channels, castors, Handles and lock etc., complete as per specifications, drawings and as directed by Engineer in charge. (P.No. 320, I.No. 39.25 of SR 2018-19) Item 39.25 Pg no 335.	Nos	5551.04	Rupees Five Thousand Five Hundred Fifty One And Paise Four Only
13	26.00	Executive Revolving Chairs Optima (Data rate Copy)	Each	23181.80	Rupees Twenty Three
14	850.00	Supplying and drawing UTP-CAT 6E LAN cable. (pg 54/9.1)	m	36.71	Rupees Thirty Six And
15	1.00	Supplying and fixing patch panels for LAN cabling 48port 10/100/1000 patch panel. (9.9.9/Pg54)	Each	19615.37	Rupees Nineteen Thousand Six
16	1.00	Supplying and fixing of network switches 48port gigabyte (managable)(9.9.1/pg54)	Each	62937.00	Rupees Sixty Two Thousand Nine
17	1.00	Supply & providing of floor mounted Rack	Each	7918.51	Rupees Seven
18	2.00	Interactive Flat Panel ViewSonic 75inch Interactive flat panel with OPS Specification for IFP : 75 Inch, 4K, 350 nits, 20 points, Intel standard OPS slot, Slim IR Dual pen Android 8.0, RAM 2GB, Storage 16GB, EEI rating A+, Contrast Ratio - 4000:1 Max., Speaker 10W X2 Native Whiteboarding tool with built-in proprietary App, Menu in Local Language, Built-in facility to convert instantly speech of the host text, Facility to convert the whole English text or part of text in to Hindi, Kannada or other Local Language, Built in tool to allow students to submit answers from their smart phones/Tablets/PC, Various options for answering - True/False, Single Choice, Multiple Choice and option to submit answer in writing, certified by Google for Education and Microsoft and bundled within the software, Google icon within the software itself for Android as well as PC Mode, each user can customized the Google as per their usage and can be saved as individual preference, Multiple User can sign in and customize as per their preference and style.	Each	26223.75	Rupees Twenty Six Thousand Two Hundred Twenty Three And Paise Seventy Five Only
19	10.00	Grid Ceiling Speakers JBL - 8 Speakers 12 W, Speaker Cable,	Each	9440.55	Rupees Nine

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
0	2.00	VGA Cable with Audio (1.8mts.) (Cable cubby to scaler below the table)	Each	5224.56	Rupees Five Thousand Two
21	2.00	Clicktronic HDMI Cable-1.5 mts. (Cable cubby to scaler below the table)	Each	2900.54	Rupees Two Thousand Nine
22	2.00	Clicktronic HDMI Cable-15 mts. from the VC to the switcher in the rack	Each	17415.20	Rupees Seventeen
23	2.00	VGA Connectors/ EP Connectors/ RS-232 Connectors/ Phoenix Connectors/ RJ-45 Connectors/ HDMI Jointer/ IEC Connectors	Each	6966.08	Rupees Six Thousand Nine Hundred Sixty
24	2.00	9U Rack-(Colour-Light Grey or Black)-9U x 600 x 600 Floor Standing Rack, Front Glass & rear Steel Door, Top cover (no fans), Side Steel Covers - removable with one fan of either side, 19 inch PDU with 6 points of 5A sockets - 1 no. with wheels	Each	12010.48	Rupees Twelve Thousand Ten And Paise Forty Eight Only
25	30.00	Vga cable	mtr	420.37	Rupees Four Hundred
26	2.00	patch plate with connectors	No	6005.24	Rupees Six Thousand
27	1.00	48 Port Switch	No	1.05	Rupees One And
28	2.00	PA System Yamaha mixer MG10	No	24020.96	Rupees Twenty Four
29	2.00	Collar / Lepel mic and Hand held Mic	No	19208.90	Rupees Nineteen
30	2.00	Supplying of Crown amplifier	No	29554.17	Rupees Twenty Nine
31	2.00	Installation, programming & Commissioning	No	26407.32	Rupees Twenty Six
32	29.00	All in One PC i5/8GB/256GB SSD +1TB HDD Win 10/21.5" Monitor Keyboard & Mouse	NO	100279.62	Rupees One Lakh(s) Two Hundred Seventy
33	1.00	Firewall	NO	99650.25	Rupees Ninety Nine
34	1.00	UPS 10KVA with 2hrs backup	NO	718530.75	Rupees Seven
35	1.00	UPS 1KVA with 2hrs backup	NO	54545.40	Rupees Fifty Four
36	2.00	Stage table	no	15839.15	Rupees Fifteen
37	2.00	Web Camera and USB Extended Cable	NO	17643.34	Rupees Seventeen
38	1.00	Internet for 12 Months for 34Pcs (1000Mbps/5000GB/per month)	LS	125874.00	Rupees One Lakh(s)
39	2.00	Wooden Podium	NO	27272.70	Rupees Twenty Seven
40	1.00	Network Face Plate, IO Connectors, RJ 45 Connectors, Network Patch Cord-1mts and 2mts	NO	36713.25	Rupees Thirty Six Thousand Seven
41	2.00	CCTV - 2nos - 2MP Camera, 4 Channel NVR - 1nos, 4Port POE Switch, HDD-4TB, required Cabling	NO	32727.24	Rupees Thirty Two Thousand Seven Hundred Twenty
42	1.00	Corridor Speakers,Mic ,Cables , Dashboard,Control Board , and all Components and accessories. (Data Rate)	NO	1311187.50	Rupees Thirteen Lakh(s) Eleven
43	0.40	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means using Dozer In area of light jungle (Vol III , P.No 07 Sl.No 2.5 A)	Ha	182358.28	Rupees One Lakh(s) Eighty Two Thousand Three Hundred Fifty Eight And Paise Twenty Eight Only
44	6750.00	De-silting tank bed/Feeder Channel/Canal in dry condition by excavating the deposited bed material and loading the same to transport vehicle (excluding cost of transportation) including cost of all machinery, labour etc., complete with all lead and all lifts (VoL IV , P.No 39 Sl.No 6.18)	Cum	53.08	Rupees Fifty Three And Paise Eight Only
45	171.00	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work In all kinds of soils Depth upto 3 m (Vol I , P.No 8 Sl.No 1.14.1)	Cum	84.24	Rupees Eighty Four And Paise Twenty Four Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
46	1589.50	Providing casing embankment using semi-pervious/ pervious soil collected in embankment area in heaps as part of disposal of excavated soil from canal in layer of 250 to 300 mm (before compaction) including cost of all materials, machinery, labour, all operations such as collection of soil, spreading in soil in layer of specified thickness , sorting-out,lavelling, breaking clods, sectioning edges/sides, watreing and compacting each layer to density control of not less than 95 percent or as stipulated by power roller etc., complete with lead upto 1 km for water. (Vol IV Item No 3.60 Pg No)	Cum	241.16	Rupees Two Hundred Forty One And Paise Sixteen Only
47	519.90	KSRRB M2500-4.1. Providing and laying pitching stones of size 0.3x 0.3x0.3 on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embackment complete as per drawing and Technical specification including cost of all material, labour, HOM complete as per specification. A.stone / Boulder MORTH specification No.2504 (Vol III Item No 16.40 Pg No 111)	Cum	1886.54	Rupees One Thousand Eight Hundred Eighty Six And Paise Fifty Four Only
48	47.88	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting,barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work In all kinds of soils Depth upto 3 m (Vol I ,P.No 8 Sl.No 1.14.1)	Cum	84.24	Rupees Eighty Four And Paise Twenty Four Only
49	4.59	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:4:8(M5) Using 40 mm nominal size graded crushed coarse aggregates (Vol I , P.No 15 Sl.No 2.1.2)	Cum	6189.22	Rupees Six Thousand One Hundred Eighty Nine And Paise Twenty Two Only
50	27.30	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Vol I , P.No 15 Sl.No 2.2.2 .1)	Cum	7832.07	Rupees Seven Thousand Eight Hundred Thirty Two And Paise Seven Only
51	10355.00	Providing Thermo-Mechanically Treated bars of grade Fe-500D or more Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members whereever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately) (Vol II , P.No 84 Sl.No 11.32) Issue Rate as on 07.04.2022	Kg	122.31	Rupees One Hundred Twenty Two And Paise Thirty One Only
52	9.00	KSRB M2500-3 :Providing and laying Filter material underneath pitching in slopes complete as per drawing and Technical specification including cost of material, machinery, labour HOM complete as per specifications. MORTH Specification No. 2504. (Vol III Item No 16.40 Pg No 111)	Cum	3919.62	Rupees Three Thousand Nine Hundred Nineteen And Paise Sixty Two Only
53	13.50	KSRRB M2500-4.1. Providing and laying Pitching on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per drawing and Technical specifications A. Stone / Boulder MORTH Specification No. 2504 (Vol III Item No 16.4A Pg No 111)	Cum	1886.54	Rupees One Thousand Eight Hundred Eighty Six And Paise Fifty Four Only

Contractor
Halappa

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
	6115.23	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (Vol III , P.No 3 Item No. 1.1)	cum	180.95	Rupees One Hundred Eighty And Paise
55	162.60	Earth work in surface excavation for stripping, seating of bund, Road way by manual means for lowering & levelling the ground for all works other than foundation & depth in Ordinary rock and soft rock upto 300mm depth as per drawing and technical specifications, including setting out, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the work. (Vol I , P.No 5 Item No. 1.2)	Cum	521.54	Rupees Five Hundred Twenty One And Paise Fifty Four Only
56	122.50	Construction of Embankment by excavating the available approved Gravel/Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work. (Vol I , P.No 7 Item No. 1.8)	Cum	463.85	Rupees Four Hundred Sixty Three And Paise Eighty Five Only
57	247.62	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates (Vol I , P.No 15 Item No. 2.1.4)	Cum	6837.69	Rupees Six Thousand Eight Hundred Thirty Seven And Paise Sixty Nine Only
58	686.00	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications. (Vol II , P.No 64 Item No. 9.31)	Sqm	1254.23	Rupees One Thousand Two Hundred Fifty Four And Paise Twenty Three Only
59	1289.00	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)	No	531.82	Rupees Five Hundred Thirty One And Paise Eighty Two Only
60	232.00	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces (Volume III , Item No : 8.10 , Page No :)	Sqm	98.08	Rupees Ninety Eight And Paise Eight Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
61	88.00	Providing and fixing of Ornamental Granite Pillar of overall height of 1250mm 200x200sqmm, Octagonal to a height of 820mm and carving design at bottom as shown in drawing .and 280mm respectively as per the approved Design and drawing including quarry cutting to the required size and transporting the same from quarry to work spot\ including loading and un loading with all lead and lift etc. complete as per design and drawing. The work shall be carried out as per design and drawing. Firmly fixed to the ground by means of properly designed foundation of size 300mm x 300mm x 300mm in 1:1.5:3 ratio cement concrete The work shall be carried out as per the engineers in charge of the work etc. and completion of the work as per directions of the Engineer-in-charge of the work.	Each	15944.04	Rupees Fifteen Thousand Nine Hundred Forty Four And Paise Four Only
62	204.00	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces (Volume III , Item No : 8.10 , Page No :)	Sqm	98.08	Rupees Ninety Eight And Paise Eight Only
63	1963.18	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts,	Kg	576.92	Rupees Five Hundred Seventy Six And Paise Ninety Two Only
64	115.23	Earth work in surface excavation for stripping, seating of bund, Road way by manual means for lowering & levelling the ground for all works other than foundation & depth in Ordinary rock and soft rock upto 300mm depth as per drawing and technical specifications, including setting out, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the work. (Volume I , Item No : 1.2 , Page No : 5)	Cum	521.54	Rupees Five Hundred Twenty One And Paise Fifty Four Only
65	277.92	Wet Mix Macadam (Plant mix method) Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. (Volume III , Item No : 4.27 , Page No : 19)	Cum	2762.30	Rupees Two Thousand Seven Hundred Sixty Two And Paise Thirty Only
66	46.09	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ m3, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing. (Volume III , Item No : 6.1 , Page No : 43)	Cum	4841.53	Rupees Four Thousand Eight Hundred Forty One And Paise Fifty Three Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
67	69.14	Cement Concrete Pavement with OPC/PPC/PSC Construction of M40 grade un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with Cement at 420 kg/m3, coarse and fine aggregate conforming to IS 383:2016, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design transported to site, laid with a paver finisher, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing (Volume III , Item No : 6.2 , Page No : 43)	Cum	10786.14	Rupees Ten Thousand Seven Hundred Eighty Six And Paise Fourteen Only
68	22050.00	Dismantling chain link fencing including removing the posts, cement concrete fedestals, foundation and stacking the useful materials safely at a distance to the appropriate disposal area as per direction of Engineer-in-charge. (Volume II , Item No. 19.58 , Page No. 169)	Kg	19.62	Rupees Nineteen And Paise Sixty Two Only
69	49.00	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) (V-2) (Volume II , Item No. 19.2.2 , Page No. 163)	cum	910.39	Rupees Nine Hundred Ten And Paise Thirty Nine Only
70	189.63	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineerin-charge. In cement mortar (Volume II , Item No. 19.9.2 , Page No. 163)	Sqm	1488.46	Rupees One Thousand Four Hundred Eighty Eight And Paise Forty Six Only
71	285.00	Earth work excavation by manual means for drains,canals, waste weir draft, approach channels, key trench, foundation of Bridges and such similar works, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, excavated surface leveled and sides neatly dressed disposing off or leveling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. In ordinary/soft rock without blasting upto 1.5 m depth (Volume I , Item No. 1.5.1 , Page No. 6)	cum	264.24	Rupees Two Hundred Sixty Four And Paise Twenty Four Only
72	185.66	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates (Volume I ,Item No. 2.1.3 ,Page No. 15)	cum	6636.92	Rupees Six Thousand Six Hundred Thirty Six And Paise Ninety Two Only
73	477.75	Providing Coursed rubble masonry (second sort) with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) (Volume II , Item No. 5.3 , Page No. 9)	cum	6076.15	Rupees Six Thousand Seventy Six And Paise Fifteen Only
74	358.47	Providing Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) (Volume II , Item No. 5.2 , Page No. 9)	cum	6474.23	Rupees Six Thousand Four Hundred Seventy Four And Paise
75	1518.00	Providing Flush/ Ruled pointing: Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge. (Volume II , Item No. 8.19.1 , Page No. 44)	Sqm	230.77	Rupees Two Hundred Thirty And Paise Seventy Seven Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Ralappa	
				in figures	in words
76	2205.00	Fabricating, providing and erecting in position of MS. Hot dip galvanized Sq. Hallow Poles of 132*132 Heavy gauge of length 3000mm with MS. Hot dip galvanized grill work as per approved design and drawing of chief architect. Using 12*75mm galvanized flat for allround frame and 20mm*20mm galvanized- forged design with square for vertical at 150mm C/C as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flat, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading with cost and conveyance of all materials, labour, machinery and incidental charges for the successful complete of the work as per the direction Engineer-in-charge of the work. (Approved Data Rate Copy Attached)	Sqm	16395.09	Rupees Sixteen Thousand Three Hundred Ninety Five And Paise Nine Only
77	112.28	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72*72*4.8mm Sq. GI Pipe frame with top pipe bending in heavy duty hydraolic press with sand packing and hot bending to form double arch as per drawing profile,20mm hot dip galvanised sq.rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq.rods and heads at top,middle and bottom. Intermediate supports of 75*12mm and 50*6mm arch bent to hot .dip galvanised flats.the work is inclusive of throughing GI.flat GIsq.rods, placing, welding all the joints including grinding,finishing metal patty,painting wo coats enamel painting.The rate is inclusive of all materials like GI sq.pipe,GI.Sq.rods,GI forged designs etc., heavy duty hinges are made out of 75mm solid sq.block assembled with 20mm dia bearing in the three places for each flop. Heavy duty locking arrangements at low places including cost of labou,pailnting,erecting charges using hoist pulley cranes with all lead and lift,loading,transportation,unloading,scaffolding charges and all other incidental charges for sucessful completion of the work as per	Sqm	22395.08	Rupees Twenty Two Thousand Three Hundred Ninety Five And Paise Eight Only
78	1.00	BASAVESHWARA (SITTING) bronze sculpture with following specification a) Making of clay modeling as per the approved schematic sketch b) Making of POP negative mould as per the approved clay model c) Making of FRP (Fiber Reinforced Plastic) casting master pattern d) Making of Bronze Metal (88% of copper and 12% of tin) casting by ABC mould by silica sand process with all necessary melting process materials e) Making of hand carving/ Chiseling grinding, brazing, antic bronze oxidizing by acid process including cost of bronze ornamental finishing f) Imported PU Poly utherin lacqor coating g) The height of the Statue would be about 5 feet height with a weight of about 1200.00 kgs (apporx) excluding weight of MS supporting fabrication work for strengthening of statue including cost of all necessary raw materials, labour, artizans and semi artizans works including erection, with all applicable taxes etc., (Including Erection and transportation charges etc.,) complete as per the direction of engineer in charge. (Data Rate Copy)	Each	4195800.00	Rupees Forty One Lakh(s) Ninety Five Thousand Eight Hundred Only
79	3.60	Earth work in surface excavation by manual means for lowering & levelling the ground by chiselling and wedging in Hard rock for all works other than foundation & depth not exceeding 100 mm as per drawing and technical specifications, including setting out, barricading, caution lights, dressing of excavated surfaces, disposing off the excavated spalls/stuff & stacking the selected spall/ stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. (Volume-1, Pg. No. 5, It. No. 1.3, PWD, SR 2021-22)	Cum	156.92	Rupees One Hundred Fifty Six And Paise Ninety Two Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
80	1.60	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications. (Volume-2, It. No. 6.4 of PWD SR 2021-22)	Cum	2955.00	Rupees Two Thousand Nine Hundred Fifty Five Only
81	21.07	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Volume-1, Pg. No. 16 & 17, It. No. 2.4.3 of PWD SR 2021-22)	Cum	7849.51	Rupees Seven Thousand Eight Hundred Forty Nine And Paise Fifty One Only
82	25.47	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Volume-1, Pg. No. 16 & 17, It. No. 2.4.3 of PWD SR 2021-22)	Cum	8721.68	Rupees Eight Thousand Seven Hundred Twenty One And Paise Sixty Eight Only
83	9.00	KSRB 2.5 : Earthwork excavation (in soil deposits) and filling sides of foundation upto plinth in layers not exceeding 20cms. in depth, compacting each deposited layer by ramming after watering with all lead and lift including cost of all labour complete as per specifications. specification. No. KBS 2.9.9 / 2.9.10.1 / 2.1.1 (P.No.7, I.No.2.12 of PW, P&IWTD SR 2018-19)	Cum	456.54	Rupees Four Hundred Fifty Six And Paise Fifty Four Only
84	4.00	Providing, fixing Ornamental Granite Column of overall height of 2585mm, 430x430sqmm @bottom, octagonal at a height of 1250mm for a height of 390mm, flower design on both faces of the pillar above the octagonal for a height of 430mm and carving design for a height of 350mm and above that 590mmx590mmx160mm pedestal cap as per the approved Design including quarrying cutting to the required size and transporting the same from quarry to work spot including loading and un loading with all lead and lift etc.., complete as per design and drawing. The work shall be carried out as per the directions of the engineers in charges	Each	43531.43	Rupees Forty Three Thousand Five Hundred Thirty One And Paise Forty Two Only
85	191.24	Providing and fixing 20mm thick gang saw water cut Lakared granite for cladding in CM 1:3 (1 cement : 3 coarse sand) proportion with a coat of rough plastering using CM 1:4 (1 cement : 4 fine sand), cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, mortar, labour for all items of work, usage charges of machinery etc., complete as per specification. (Item 10.19 P.No 72)	sqm	4052.30	Rupees Four Thousand Fifty Two And Paise Thirty Only

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
86	30.00	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) 300 x 300 x 150 mm Kerb Stone (Volume III , Item No. 21-A 8.7 , Page No. 148)	m	375.00	Rupees Three Hundred Seventy Five Only
87	12.00	High quality long throw multi color wash light, Protection Rating : IP65, Additional wall mount yoke arrangements for fixing the lights. Power consumption : 50W, CCT : RGBW, Beam Angle 25° / 45°, Control : DMX512, Die casted / extruded aluminium body, Optics Designed to minimize hot spots & fringing in color mixing applications. Power Input : DC 24V (without DC Driver) Code: AK Wash 50 RGBW / Equivalent	Each	17720.96	Rupees Seventeen Thousand Seven Hundred Twenty And Paise Ninety Six Only
88	3.00	High quality spot light, Power : 12W, CCT : RGBW, Protection Rating : IP65, additional wall mount yoke arrangements for fixing the lights. Beam Angle 15°/25°, Body : Die casted / extruded aluminium, Optics Designed to minimize hot spots. Power Input : DC 110-230V,50Hz. Code: AK SL 12 RGBW / Equivalent	Each	8916.08	Rupees Eight Thousand Nine Hundred Sixteen And Paise Eight Only
89	4.00	High quality long throw multi color linear wash light, Protection Rating : IP65, Additional wall mount yoke arrangements for fixing the lights. Power consumption : 80W, CCT : RGBW, Beam Angle 25°, Control : DMX512, Die casted / extruded aluminium body, Power Input : DC 24V (without DC Driver) Code: AK IP LW 80 RGBW / Equivalent	Each	26049.62	Rupees Twenty Six Thousand Forty Nine And Paise Sixty Two Only
90	41.00	High quality Linear Profile light, Protection Rating : IP65,Power loopin and loop out for easy of connections. Power : 15W, 17mm CCT : RGBW, Beam Angle 120°, Body : Extruded aluminium. Power Input : DC 24V (without DC Driver) Code: AK IP LW 15 RGB / Equivalent	Each	4797.90	Rupees Four Thousand Seven Hundred Ninety Seven And Paise Ninety Only
91	33.00	High quality 360° LED Window Trick Light - Surface Mounted, RGBW, DMX Compatible, Working Voltage: DC24V, Power: 5W x 4CH, (Without DC Power Drive) Code: AK TL 360 RGBW / Equivalent	Each	23828.90	Rupees Twenty Three Thousand Eight Hundred Twenty Six
92	60.00	High quality long throw multi color linear wash light, Protection Rating : IP65, Additional wall mount yoke arrangements for fixing the lights. Power consumption : 30W, CCT : RGBW, Beam Angle 25°, Control : DMX512, Die casted / extruded aluminium body, Power Input : DC 24V (without DC Driver) Code: AK IP LW 30 RGBW / Equivalent	Each	18495.09	Rupees Eighteen Thousand Four Hundred Ninety Five And Paise Nine Only
93	45.00	DC power driver for the above Lights, Power : 200W, Input : AC 110-240V AC, 50Hz, Output : DC 12/24V, Protection rating: IP65, Surge protection : MW 4KV, MW 6KV / Equivalent	Each	8257.33	Rupees Eight Thousand Two Hundred Fifty Seven
94	20.00	High quality DMX decoder, Power Input : DC 24V, Protection rating : IP65.	Each	4585.03	Rupees Four Thousand Five
95	500.00	Flexible Multicore Cable 3C X 1.5Sq.mm	M	28.85	Rupees Twenty Eight
96	250.00	Flexible Multicore Cable 3C X 2.5Sq.mm	M	47.20	Rupees Forty Seven
97	600.00	5 core DMX armoured cable comprises twisted pairs with shield support for carrying of data. DMX512 cable is used for connecting all light consoles that use DMX 512 standard data transmission. (As per actuals depending upon the site condition)	each	317.83	Rupees Three Hundred Seventeen And Paise Eighty Three Only
98	105.00	IP65 "T" power connectors easy and extremely precise locking system. High impact materials - long- lasting and reliable	each	1058.29	Rupees One Thousand Fifty Six
99	124.00	IP65 "T" power connectors having 3/4 pole cable connector, chuck type strain relief, Current rating 20 A rms continuous, Easy and extremely precise locking system "Quick Lock" High impact materials - long-lasting and reliable	each	1760.14	Rupees One Thousand Seven Hundred Sixty And Paise Fourteen Only
100	140.00	IP65 DMX connectors having 3/5 pole cable connector, Male/Female connector with improved latch, cage type contacts, "solder stop" for easy soldering, and additional ground contact for best contact integrity between chassis and cable connector. More durable housing for maximum reliability	each	1137.06	Rupees One Thousand One Hundred Thirty Seven And Paise Six Only
101	20.00	IP65 "XLR" male connectors having 3/5 pole cable connector, Male/Female connector with improved latch, cage type contacts, "solder stop" for easy soldering, and additional ground contact for best contact integrity between chassis and cable connector. More durable housing for maximum reliability.	each	722.73	Rupees Seven Hundred Twenty Two And Paise Seventy Three Only

Halappa
Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Saheb	
				In figures	In words
102	6.00	IP65 "XLR" female connectors having 3/5 pole cable connector. Male/Female connector with improved latch, cage type contacts, "solder stop" for easy soldering, and additional ground contact for best contact integrity between chassis and cable connector. More durable housing for maximum reliability.	each	722.73	Rupees Seven Hundred Twenty Two And Paise Seventy Three Only
103	12.00	Waterproof power junction box /power cable terminal box, IP65 made up of rugged, non-corrosive, high impact polycarbonate, molded nylon encases connectors that use screw compression to secure the wires, protection against water jets and dust from all directions, includes 5 Way min 10A connector terminal block Max. dimension : 80 * 250 * 85mm	each	1208.39	Rupees One Thousand Two Hundred Eight And Paise Thirty Nine Only
104	2.00	DMX isolator or splitter provides isolated optical DMX splitter provides 8 outputs from a 1 input and Input voltage: AC 110 to 220 V, 50 Hz, Product features: Group 1 & group 8 DMX signal change.	each	35219.55	Rupees Thirty Five Thousand Two Hundred Nineteen
105	1.00	Master Controller consits of 24 Physical Faders to control atleast 96 channels 4 Individual page control switches Master control fader Black out mode Scene saving option upto 96 memories LCD display Smooth movement faders Easy access key pads DmX 512 protocol, 5 Pin XLR Output Optional chase & multifunction keys Sequence mode select. Code: CX – 12 / equivalent	each	203407.14	Rupees Two Lakh(s) Three Thousand Four Hundred Seven And Paise Fourteen Only
106	1.00	Custom Computer for show programming with required graphic card, memroy, software	each	132692.18	Rupees One Lakh(s) Thirty Two Thousand
107	1.00	Additional accessories, Technicians, Electricians, Labour, for installing the lights as per the final drawing/site condition consisting of clamps, brackets, angles, conduites, joints, hardwares like fasteners, nut & bolts etc.,	each	209790.00	Rupees Two Lakh(s) Nine Thousand Seven Hundred Ninety Only
108	110.50	Dismantling of Kerb Stone Dismantling kerb stone by manual means and disposal of dismantled material with all lifts and lead (Volume III , Item No. 2.21 , Page No. 10)	Mtr	20.77	Rupees Twenty And Paise Seventy Seven Only
109	20.06	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge. (Volume II , Item No. 19.2.1 , Page No. 163)	Cum	1470.00	Rupees One Thousand Four Hundred Seventy Only
110	148.10	Dismantling tile work in floors and roofs laid in cement mortar including stacking material to the appropriate disposal area as per direction of Engineer-in-charge. For thickness of tiles 10 mm to 25 mm	Sqm	42.70	Rupees Forty Two And Paise Seventy Only
111	247.00	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)	Nos	531.82	Rupees Five Hundred Thirty One And Paise Eighty Two Only
112	2489.60	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate sections and other sections of approved make conforming to IS: 733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For Fixed Portion :Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) including cost of materials, labour, usage charges of machinery complete as per specifications. (Volume II , Item No. 11.35.1.3 , Page No.86)	Kgs	456.92	Rupees Four Hundred Fifty Six And Paise Ninety Two Only

Malappa
Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
113	174.00	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. Depth exceeding 1.5m, but not exceeding 3 m	cum	229.62	Rupees Two Hundred Twenty Nine And Paise Sixty Two Only
114	3.30	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (Volume-1, Pg. No. 16 & 17, It. No. 2.4.3 of PWD SR 2021-22)	cum	7994.88	Rupees Seven Thousand Nine Hundred Ninety Four And Paise Eighty Eight Only
115	28.80	Providing Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	5566.15	Rupees Five Thousand Five Hundred Sixty Six And Paise Fifteen Only
116	174.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	235.38	Rupees Two Hundred Thirty Five And Paise Thirty Eight Only
117	38.70	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete.	Cum	2511.93	Rupees Two Thousand Five Hundred Eleven And
118	120.96	Providing and fixing M.S. grills of required pattern in frames of win- dows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings / wooden frames with rawl plugs screws etc.	kg	165.00	Rupees One Hundred Sixty Five Only
119	5.76	Providing & fixing of 2-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having a overall size of 60mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm X 58mm with GI reinforcement of 1mm for the frame and 1.5 mm for the sash. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with touch lock. Wall thickness of frame & sash shall be of 2-2.5 mm. Maximum possible size – 1819mm x 1819mm (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	sqm	7397.31	Rupees Seven Thousand Three Hundred Ninety Seven And Paise Thirty One Only
120	117.68	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	1336.49	Rupees One Thousand Three Hundred Thirty Six And Paise Forty Nine Only

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
121	0.25	Providing Mathi/Nandi wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.	Cum	86935.30	Rupees Eighty Six Thousand Nine Hundred Thirty Five And Paise Thirty Only
122	8.19	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures)	Sqm	5256.92	Rupees Five Thousand Two Hundred Fifty Six And Paise Ninety Two Only
123	126.60	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	sqm	354.24	Rupees Three Hundred Fifty Four And Paise Twenty Four Only
124	436.72	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. ** Polished Granite stone slab Black, Cherry Red, Brown, Cat Eye, River Pink or equivalent.	sqm	3324.23	Rupees Three Thousand Three Hundred Twenty Four And Paise Twenty Three Only
125	178.50	Providing, laying & fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.	sqm	1314.23	Rupees One Thousand Three Hundred Fourteen And Paise Twenty Three Only
126	1388.21	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.	sqm	95.77	Rupees Ninety Five And Paise Seventy Seven Only
127	80.38	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.	Sqm	859.62	Rupees Eight Hundred Fifty Nine And Paise Sixty Two Only
128	150.80	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (Volume-3, Pg. No. 3, It. No. 1.1, PWD, SR 2021-22)	Cum	190.91	Rupees One Hundred Ninety And Paise Ninety One Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
129	1.00	DIESEL GENERATOR SET Supplying, installing, testing and commissioning of Diesel Generator set with following specifications. Power rating as per standard reference condition as per-BS 5514 / ISO 3046 / ISO 8528 & IS 1002 / ISO 3046 Generator set specifications Engine: Diesel generating set are rated at 1500RPM and conform to ISO 8528 specifications. The engines are radiator cooled, four stroke and multi cylinder, conforming to ISO 3046. The scope of supply includes: Electrical starter motor 12V DC Battery charging alternator, Bosch fuel system with mechanical governor, A1 Class. Spin-on lube oil filter, Spin-on dual fuel filter with water separator, Turbocharger, Charge air cooler, Silencer (Hospital grade),Dry type air cleaner, Shutoff coil, Flywheel and flywheel housing, First fill of lube oil and coolant, Safety for low lube oil pressure, Safety for high water temperature, Permissible overload of 10% for one hour in 12 hours of operation Capacity of Fuel Tank: Fuel tank suitable for 8 hours of operation 50KVA/40kw	Each	638249.36	Rupees Six Lakh(s) Thirty Eight Thousand Two Hundred Forty Nine And Paise Thirty Six Only
130	200.00	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Each	126.92	Rupees One Hundred Twenty Six And Paise Ninety Two Only
131	24.00	Providing & fixing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete as per design drawings (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per the direction of Engineer in charge. 0.63 mm thick with zinc coating not less than 275 g/ m^2	Sqm	917.31	Rupees Nine Hundred Seventeen And Paise Thirty One Only
132	1.00	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : 510x1040 mm bowl depth 250 mm	Kgs	5734.61	Rupees Five Thousand Seven Hundred Thirty Four And Paise Sixty One
133	1.00	Providing and fixing C.P. brass long body bib cock of approved qualityb conforming to IS standards and weighing not less than 690 g.	Each	777.69	Rupees Seven Hundred Seventy
134	50.00	Providing and Fixing CPVC pipes, Internal work-Exposed on Wall 20mm nominal dia pipes (Vol II , Item No . 13.31.2) 1st Corrigenda w.e.f 21-04-2022 .	Mtr	275.77	Rupees Two Hundred Seventy Five And Paise Seventy Seven
135	2.76	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	4223.07	Rupees Four Thousand Two Hundred Twenty Three And Paise Seven Only
136	12600.00	Brass Name Board (Data Rate Approved)	Sqm	26.22	Rupees Twenty Six
137	2.00	The MEG 14-40 is a matt-black-painted, 40 cm gooseneck microphone with one flexible section, an XLR connection and built-in Sennheiser KE10 cardioid microphone capsule. (SENNHEISER) as per specifications and directions of the Engineer in charge. (Data Rate to Be Approved).	No	25575.08	Rupees Twenty Five Thousand Five Hundred Seventy Five And Paise Eight Only
138	2.00	The MAT 133-S is a sturdy, wired table stand that provides a stable base for XLR-3 gooseneck microphones. (SENNHEISER) as per specifications and directions of the Engineer in charge. (Data Rate to Be Approved).	No	22082.90	Rupees Twenty Two Thousand Eighty Two And Paise Ninety Only

Halappa
Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
139	2.00	UHF Wireless Handheld Microphone.(SENNHEISER) as per specifications and directions of the Engineer in charge. (Data Rate to Be Approved).	No	44477.71	Rupees Forty Four Thousand Four Hundred Seventy
140	20.00	2-way Cabinet Loudspeaker, LF Driver 5.25" & HF Driver 1" Max Power Handling 100W @ 8 Ohms ; Multiple 100V Taps : 40W/20W/10W; Frequency range 65Hz – 20Khz ; Sensitivity 87 dB and Max SPL 104 dB; Coverage of 110° x 110° (H X V) ; IP55 Rated; Operating Temperature -20°C to 70°C; ABS Plastic Housing with steel grill. Mounting Bracket Included. Black.	No	12122.02	Rupees Twelve Thousand One Hundred Twenty Two And Paise Two Only
141	2.00	Single Channel Class D Amplifier; Power Output 240 W / CH @ 100V; Protection : DC Shorcuit, Over load, Over heat, Signal Limiting, Temperature controlled Fan; THD < 1%; SN Ratio > 90 dB; Crosstalk < 80 ; Input : XLR Connector with link ; Output : 4-pin Terminal; Switch Mode Power Supply	No	79618.36	Rupees Seventy Nine Thousand Six Hundred Eighteen And Paise Thirty Six Only
142	1.00	16-Channel Mixing Console. (YAMAHA) as per specifications and directions of the Engineer in charge. (Data Rate to be Approved)	No	63125.81	Rupees Sixty Three Thousand One
143	2.00	Installation Material with Speaker cables, Mic Cables Connectors . Complete as per specifications and directions of the Engineer in charge	No	83548.87	Rupees Eighty Three Thousand Five
144	277.52	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. (Item No8.2.1, Page no 41 of PWD SR 2021-22)	Sqm	291.93	Rupees Two Hundred Ninety One And Paise Ninety Three Only
145	308.97	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specifications and directions of the Engineer in charge. (First Floor)	Sqm	294.58	Rupees Two Hundred Ninety Four And Paise Fifty Eight Only
146	263.92	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specifications and directions of the Engineer in charge. (Second Floor)	Sqm	297.23	Rupees Two Hundred Ninety Seven And Paise Twenty Three Only
147	243.47	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 900mm,complete as per Specification.and directions of the Engineer in charge.(First Floor)	Sqm	3354.45	Rupees Three Thousand Three Hundred Fifty Four And Paise Forty Five Only
148	232.23	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 900mm,complete as per Specification.and directions of the Engineer in charge.(Second Floor)	Sqm	3384.67	Rupees Three Thousand Three Hundred Eighty Four And Paise Sixty Seven Only

Halappa

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
149	209.17	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 900mm,complete as per Specification.and directions of the Engineer in charge.(Third Floor)	Sqm	3414.89	Rupees Three Thousand Four Hundred Fourteen And Paise Eighty Nine Only
150	22.49	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,complete as per Specificationand directions of the Engineer in charge.(Item No 14.51, Page no 110 of PWD SR 2018-19)	Sqm	5141.53	Rupees Five Thousand One Hundred Forty One And Paise Fifty Three Only
151	16.49	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,complete as per Specificationand directions of the Engineer in charge.(First Floor) (Item No 14.51, Page no 110 of PWD SR 2018-19)	Sqm	5188.28	Rupees Five Thousand One Hundred Eighty Eight And Paise Twenty Eight Only
152	16.49	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,complete as per Specification.and directions of the Engineer in charge.(Second Floor) (Item No 14.51, Page no 110 of PWD SR 2018-19)	Sqm	5235.02	Rupees Five Thousand Two Hundred Thirty Five And Paise Two Only
153	291.51	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 (1 cement : 3 coarse sand) proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete.. - Ground Floor (Item No 10.18, Page no 72 of PWD SR 2021-22)	Sqm	3545.77	Rupees Three Thousand Five Hundred Forty Five And Paise Seventy Seven Only
154	245.31	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 (1 cement : 3 coarse sand) proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete.. - First Floor (Item No 10.18, Page no 72 of PWD SR 2021-22)	Sqm	3578.00	Rupees Three Thousand Five Hundred Seventy Eight Only
155	240.75	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 (1 cement : 3 coarse sand) proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete.. - Second Floor (Item No 10.18, Page no 72 of PWD SR 2021-22)	Sqm	3610.24	Rupees Three Thousand Six Hundred Ten And Paise Twenty Four Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
156	30.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including pointing the joints with white cement and matching pigments etc., complete..(Item No 9.11, Page no 60 of PWD SR 2021-22)	Sqm	891.93	Rupees Eight Hundred Ninety One And Paise Ninety Three Only
157	18.45	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including pointing the joints with white cement and matching pigments etc., complete..(First Floor)	Sqm	900.03	Rupees Nine Hundred And Paise Three Only
158	21.90	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including pointing the joints with white cement and matching pigments etc., complete...(Second Floor)	Sqm	908.14	Rupees Nine Hundred Eight And Paise Fourteen Only
159	129.02	Providing skirting, dadooing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. (Item No 9.39, Page no 65 of PWD SR 2021-22)	Sqm	2394.23	Rupees Two Thousand Three Hundred Ninety Four And Paise Twenty Three Only
160	141.90	Providing skirting, dadooing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. (First Floor)	Sqm	2415.99	Rupees Two Thousand Four Hundred Fifteen And Paise Ninety Nine Only
161	120.68	Providing skirting, dadooing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. (Second Floor)	Sqm	2437.76	Rupees Two Thousand Four Hundred Thirty Seven And Paise Seventy Six Only
162	638.05	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.(Item No 8.51, Page no 50 of PWD SR 2021-22) (First Floor)	Sqm	96.64	Rupees Ninety Six And Paise Sixty Four Only
163	597.82	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.(Item No 8.51, Page no 50 of PWD SR 2021-22)(Second Floor)	Sqm	97.51	Rupees Ninety Seven And Paise Fifty One Only
164	170.15	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.(Item No 8.51, Page no 50 of PWD SR 2021-22) - Terrace Floor	Sqm	98.38	Rupees Ninety Eight And Paise Thirty Eight Only
165	638.05	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two coats) over and including water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Item No 8.25, Page no 45 of PWD SR 2021-22)-First Floor	Sqm	122.26	Rupees One Hundred Twenty Two And Paise Twenty Six Only

Contractor

Halappa

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
166	597.82	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two coats) over and including water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Item No 8.25, Page no 45 of PWD SR 2021-22)- Second Floor	Sqm	123.36	Rupees One Hundred Twenty Three And Paise Thirty Six Only
167	258.95	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two coats) over and including water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Item No 8.25, Page no 45 of PWD SR 2021-22)- Terrace Floor	Sqm	124.46	Rupees One Hundred Twenty Four And Paise Forty Six Only
168	270.84	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two coats applied @ 1.43 ltr/10 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Item No 8.30, Page no 45 of PWD SR 2021-22) -first floor	Sqm	158.35	Rupees One Hundred Fifty Eight And Paise Thirty Five Only
169	272.25	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two coats applied @ 1.43 ltr/10 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Item No 8.30, Page no 45 of PWD SR 2021-22) - Second Floor	Sqm	159.78	Rupees One Hundred Fifty Nine And Paise Seventy Eight Only
170	248.87	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two coats applied @ 1.43 ltr/10 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (Item No 8.30, Page no 45 of PWD SR 2021-22) - Third Floor	Sqm	161.20	Rupees One Hundred Sixty One And Paise Twenty Only
171	18.45	.1 Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.(Item No 15.1, Page no 133 of PWD SR 2021-22) - first floor	Sqm	867.43	Rupees Eight Hundred Sixty Seven And Paise Forty Three Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
172	21.90	.1 Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC.Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.(Item No 15.1, Page no 133 of PWD SR 2021-22) - Second Floor	Sqm	875.24	Rupees Eight Hundred Seventy Five And Paise Twenty Four Only
173	3.94	KSRB 8.5 : Providing and laying cinder concrete in cement 1:15 (1 cement : 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications.	Cum	2327.31	Rupees Two Thousand Three Hundred Twenty Seven And Paise
174	5.54	KSRB 8.5 : Providing and laying cinder concrete in cement 1:15 (1 cement : 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications.	Cum	2348.46	Rupees Two Thousand Three Hundred Forty Eight And Paise Forty Six
175	6.57	KSRB 8.5 : Providing and laying cinder concrete in cement 1:15 (1 cement : 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications.	Cum	2369.62	Rupees Two Thousand Three Hundred Sixty Nine And Paise Sixty Two
176	5.54	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and directions of the Engineer in charge(First Floor)	Cum	6899.84	Rupees Six Thousand Eight Hundred Ninety Nine And Paise Eighty Four Only
177	6.57	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and directions of the Engineer in charge(Second Floor)	Cum	6962.01	Rupees Six Thousand Nine Hundred Sixty Two And Paise One Only
178	16.07	Providing and fixing 30 mm thick both side commercial flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification.(Item No 12.57.3, Page no 104 of PWD SR 2021-22)	Sqm	3043.84	Rupees Three Thousand Forty Three And Paise Eighty Four Only
179	13.86	Providing and fixing 30 mm thick both side commercial flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification.(Item No 12.57.3, Page no 104 of PWD SR 2021-22) - First Floor	Sqm	3071.52	Rupees Three Thousand Seventy One And Paise Fifty Two Only

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
180	12.60	Providing and fixing 30 mm thick both side commercial flush door shutter made out of solid core block board type, well seasoned , chemicaly treated frame alround door shutters covered with cross bonded wooden sheets (liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification.(Item No 12.57.3, Page no 104 of PWD SR 2021-22) -Second Floor	Sqm	3099.19	Rupees Three Thousand Ninety Nine And Paise Nineteen Only
181	9.45	Providing & fixing 30mm thick factory made rigid foam Prelam Panelled Door Shutters with both side prelam made from M.S. tube of 19x19mm, 19 gauge for stiles and 15x15mm for top & bottom rails, covered with heat moulded Prelaminated PVC C Channel of 5mm thick sheet & 30x50mm wide to form stiles & 5mm thick & 75mm wide Prelaminated PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, Sealed to the stiles & rails with PVC Designer beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer (Item No 12.55.1, Page no 104 of PWD SR 2021-22)	Sqm	4388.08	Rupees Four Thousand Three Hundred Eighty Eight And Paise Eight Only
182	15.12	Providing & fixing 30mm thick factory made rigid foam Prelam Panelled Door Shutters with both side prelam made from M.S. tube of 19x19mm, 19 gauge for stiles and 15x15mm for top & bottom rails, covered with heat moulded Prelaminated PVC C Channel of 5mm thick sheet & 30x50mm wide to form stiles & 5mm thick & 75mm wide Prelaminated PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, Sealed to the stiles & rails with PVC Designer beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer (Item No 12.55.1, Page no 104 of PWD SR 2021-22) -First Floor	Sqm	4427.97	Rupees Four Thousand Four Hundred Twenty Seven And Paise Ninety Seven Only
183	13.23	Providing & fixing 30mm thick factory made rigid foam Prelam Panelled Door Shutters with both side prelam made from M.S. tube of 19x19mm, 19 gauge for stiles and 15x15mm for top & bottom rails, covered with heat moulded Prelaminated PVC C Channel of 5mm thick sheet & 30x50mm wide to form stiles & 5mm thick & 75mm wide Prelaminated PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, Sealed to the stiles & rails with PVC Designer beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer (Item No 12.55.1, Page no 104 of PWD SR 2021-22)- Second Floor	Sqm	4467.86	Rupees Four Thousand Four Hundred Sixty Seven And Paise Eighty Six Only

Contractor

Scanned by TapScanner

No	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
184	24.82	UPVC WINDOWS Providing & fixing of 3-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size – 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made) (Item No 12.9, Page no 110 of PWD SR 2021-22)	Sqm	8353.84	Rupees Eight Thousand Three Hundred Fifty Three And Paise Eighty Four Only
185	35.46	UPVC WINDOWS Providing & fixing of 3-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size – 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made) (Item No 12.9, Page no 110 of PWD SR 2021-22) - First Floor	Sqm	8429.78	Rupees Eight Thousand Four Hundred Twenty Nine And Paise Seventy Eight Only
186	36.00	UPVC WINDOWS Providing & fixing of 3-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size – 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made) (Item No 12.9, Page no 110 of PWD SR 2021-22) - Second Floor	Sqm	8505.73	Rupees Eight Thousand Five Hundred Five And Paise Seventy Three Only

Halappa

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. C Halappa	
				In figures	In words
187	121.18	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.. - First Floor	Kg	582.17	Rupees Five Hundred Eighty Two And Paise Seventeen Only
188	121.18	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.. - Second Floor	Kg	587.41	Rupees Five Hundred Eighty Seven And Paise Forty One Only
189	10280.10	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge. (Vol II , Page No. 81 Item No . 11.16.3)	Kg	130.39	Rupees One Hundred Thirty And Paise Thirty Nine Only

Contractor

Scanned by TapScanner